

**Residential complex, Midland, ON**



**Midland Halfway House, Mar 2009**

**Project Highlights**

→ Radiant floor topping application to level two floors in pre-cast residential complex.

→ **DAROTopp®** installed 45mm topping on slip-sheet over tubing - app 12,000ft<sup>2</sup>

→ **DAROTopp®** selected based on overall **performance**; completely level/smooth surface with no control joints or sawcuts; **energy savings** due to **high conductivity** of topping and long-term **guarantee of no cracks**. Floor completely leveled, ready for ceramics and vinyl tile with no skim coating necessary for tiling.

- **DAROTopp®** installed 45–50mm overpour on **radiant floor** tubing over slip-sheet on 2 level pre-cast structure.
- Owner:
- Contractor: Innovative Home Design
- Architect:
- Applicator: Georgian Concrete